



राष्ट्रीय प्रौद्योगिकी संस्थान - आंध्रप्रदेश
NATIONAL INSTITUTE OF TECHNOLOGY ANDHRA PRADESH
Near National Highway No. 16, Kadakatla, Tadepalligudem – 534101
West Godavari District, Andhra Pradesh

Ref. No.: NITANP/SMMD/Tender/2022-23/ **59**

Date: 20.03.2023

TENDER ENQUIRY**Sub:** Construction of Contract Base for Civil Engineering Labs- Quotation invited –Regarding.

Please send your lowest quotation for the above work as per the details attached in **Annexure-1**. The quotation is to be sent in a sealed envelope to the following address:

**C/o Tender Box
Material Management & Disposal Section,
Sardar Vallabhbai Patel Administrative Building
NATIONAL INSTITUTE OF TECHNOLOGY, ANDHRA PRADESH,
Near National Highway No. 16, Kadakatla,
TADEPALLIGUDEM – 534101
West Godavari District, Andhra Pradesh.**

The quotation has to be sent by Post (Ordinary / Register / Speed Post) or drop in Tender Box physically. (Any other mode will not be accepted)

The envelope must be superscribed as **“QUOTATION”** at the center of the envelope and the above **reference number at left top** along with the name of the tender on the envelope. Quotations without the above superscription **will not be accepted**.

The last date to receive the sealed quotation is 10.04.2023.

Annexure-1


Construction of Contract Base for Civil Engineering Labs

S. No	Description	Qty	Units
1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :		
	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size)	9.85	cum
2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :		
	1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)	7.8	cum
3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size)	1.84	cum
4	Centering and shuttering including strutting, propping etc. and removal of form for :		
	Foundations, footings, bases of columns, etc. for mass concrete	108.13	sqm
5	Steel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory/workshop to construction site including placing in position and binding all complete upto plinth level.		
	Thermo-Mechanically Treated bars of grade Fe-500D or more.		
	Overall RCC items	2080	kg
6	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:		
	Cement mortar 1:4 (1 cement : 4 coarse sand)	0.16	cum
7	15 mm cement plaster on the rough side of single or half brick wall of mix :		
	1:4 (1 cement: 4 fine sand)	1.22	sqm
8	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	6.83	cum
9	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.		
	Granite of any colour and shade, Area of slab upto 0.50 sqm	26.55	sqm

While sending your lowest quotation – please specify the following:

1. Sales Tax : Inclusive
- GST : Indicate prevailing tax on percentage basis.
2. Excise Duty :
3. Rates
 - a) F.O.R. Destination/
 - b) Estimated Packing, Forwarding and Freight Charges in case of Ex-works only, may be mentioned on percentage basis.
4. Insurance : Inclusive/ indicate on percentage basis, in case payable by the Institute.
5. Preferred terms of payment (institute rules permit to pay on Receipt of materials in good condition/completion of the work):
6. Recommended mode of transport :
7. Discount offered, if any :
8. Validity of the offer :
9. Firm schedule of completion of work :
10. Detailed drawings / catalogues / Leaflets / literature / samples may be furnished wherever feasible / required
11. Please indicate clearly whether the rates quoted herein are the same as applicable to DGS & D / Government Department / Other Public Sector Undertakings.
12. The supplier shall invariably furnish the **Certificate of Clearance of GST Registration number along with the quotations.**
13. Please mention the Quotation number and name of the item/s (in brief) on your envelope when submitting your quotation to the Institute
14. Please note that the Director reserves the right to modify or alter the specifications and also to reject any or all the Quotations without assigning any reasons thereto.
15. The suppliers / firms are informed not to call on us without prior appointment.
16. The Institute is not responsible for delays / loss in postal transit or due to any other reasons.
17. Any Violation in the terms and conditions, the bidder will be made ineligible for the contract.

Yours faithfully,



Head of the Department

सह अधिष्ठाता / Associate Dean
CENTRAL STORES & PURCHASE SECTION
NIT Andhra Pradesh



